

SECTION 01560

TEMPORARY CONTROLS

1.01 SECTION INCLUDES.....1

1.02 RELATED SECTIONS.....1

1.03 WATER CONTROL.....1

1.04 DUST CONTROL.....1

1.05 EROSION AND SEDIMENT CONTROL.....1

1.06 POLLUTION CONTROL.....1

1.07 SAFETY FENCING.....2

1.08 WINTER CONTROL.....2

SECTION 01560

TEMPORARY CONTROLS

PART 1 - GENERAL

1.01 SECTION INCLUDES

- A. Water Control.
- B. Dust Control.
- C. Erosion and Sediment Control.
- D. Pollution Control.
- E. Winter Control

1.02 RELATED SECTIONS

- A. Section 01010 – Summary of Work.
- B. Section 01039 – Coordination and Meetings Project coordination.

1.03 WATER CONTROL

- A. Grade site to drain. Maintain excavations free of water. Provide, operate, and maintain pumping equipment.
- B. Protect site from puddling or running water. Provide water barriers as required to protect site from soil erosion.

1.04 DUST CONTROL

- A. Execute Work by methods to minimize raising dust from construction operations.
- B. Provide positive means to prevent air-borne dust from dispersing into atmosphere.

1.05 EROSION AND SEDIMENT CONTROL

- A. The project must comply with the Terms and Conditions of an erosion sediment control plan developed for this project. This plan is appended to Section 02270 – Slope Protection and Erosion Control of Division 2.
- B. Plan and execute construction by methods to control surface drainage from cuts and fills, from borrow and waste disposal areas. Prevent erosion and sedimentation. Adhere to the manual Stormwater Management for Maine: Best Management Practices as published by the Maine Department of Environmental Protection.
- C. Minimize amount of bare soil exposed at one time.
- D. Provide temporary measures such as berms, dikes, and drains, to prevent water flow.
- E. Construct fill and waste areas by selective placement to avoid erosive surface silts or clays.
- F. Periodically inspect earthwork to detect evidence of erosion and sedimentation; promptly apply corrective measures.

1.06 POLLUTION CONTROL

- A. Provide methods, means, and facilities to prevent contamination of soil, water, and atmosphere from discharge of noxious, toxic substances, and pollutants produced by construction operations.

1.07 SAFETY FENCING

- A. Provide temporary safety fencing to segregate the work area from other portions of the site.
(COMPLETE AS APPLICABLE FOR EACH PROJECT)

1.08 WINTER CONTROL

- A. The project, if to be constructed during the permit from October 15 to April 30, must include winter control provisions. The provisions for this project include ***(COMPLETE AS APPLICABLE FOR EACH PROJECT)***

---END OF SECTION 01560---