

**SECTION 01570**

**TRAFFIC CONTROL AND SIGNAGE**

1.01 GENERAL REQUIREMENTS..... 1

2.01 SIGNS, BARRICADES, AND WARNING DEVICES ..... 1

3.01 MAINTENANCE OF TRAFFIC ..... 1

3.02 DETOURS ..... 1

3.03 SCHEDULING OF WORK ..... 1

3.04 SIGNS, BARRICADES, AND WARNING DEVICES ..... 1

3.05 EXISTING SIGNS ..... 2

## SECTION 01570

### TRAFFIC CONTROL AND SIGNAGE

#### **PART 1 – GENERAL**

##### **1.01 GENERAL REQUIREMENTS**

- A. *(COMPLETE AS APPLICABLE FOR THE SPECIFIC PROJECT)*

#### **PART 2 – PRODUCTS**

##### **2.01 SIGNS, BARRICADES, AND WARNING DEVICES**

- A. General: Comply with requirements in “Manual on Uniform Traffic Control Devices” published by Department of Transportation, Federal Highway Administration and requirements of the Maine Department of Transportation.

#### **PART 3 – EXECUTION**

##### **3.01 MAINTENANCE OF TRAFFIC**

- A. General: Maintain at least one-way traffic through the work area during working hours and two way traffic on nights, weekends, and holidays.
- B. Reserved.
- C. Emergency vehicles have the right-of-way at any time and shall be accommodated.

##### **3.02 DETOURS**

- A. General: Detours are not allowed on this project. *(REVISE FOR SPECIFIC PROJECT IF APPLICABLE)*

##### **3.03 SCHEDULING OF WORK**

- A. Schedule all work to minimize disruptions and to allow access to all buildings and in accordance with other portions of this contract.
- B. Revise the plan of work, if, in the opinion of the Engineer, Owner, or other regulatory agency, it will create traffic hazard or an unreasonably long delay.

##### **3.04 SIGNS, BARRICADES, AND WARNING DEVICES**

- A. General: The contractor shall erect appropriate signs to warn traffic of construction zone and/or detours. Placement of necessary signs shall be at the discretion of the Engineer/Owner and shall be done so without added cost to the Owner.
- B. Provide adequate warning signs, barricades, signal lights, and take other necessary precautions for the safety of the public.
- C. Provide and illuminate suitable warning signs to show where construction, barricades, or detours exist.
- D. Signal lights: Illuminate at all barricades and obstructions from sunset to sunrise.
- E. Maintain necessary signs, and signs required by the Maine DOT or the City of Saco, barricades, lights, and other safety precautions during authorized suspension of the work, week-ends, holidays, or other times when construction work is not in progress.

**3.05 EXISTING SIGNS**

- A. Temporarily Reset and Maintain street signs which must be moved during construction. Relocate signs so that no traffic hazards are created.
- B. Permanently reset signs at designated locations prior to completion of work unless stipulated otherwise by the contract drawings.

**---END OF SECTION 01570---**